



1 Verify o-rings are seated on front and rear bearings of TA



2 Insert turbine assembly into head housing



3 Screw on back cap, refer to section 5 of the TA Installation Procedure

